



**System should be installed on solid concrete floor or VCT covered concrete floor.
Any existing carpet must be removed prior to installation at the rail locations.**

Floor levelness should meet standard General Contractor code of 1/8" over 10'.

Elevation

77 3/4" uprights

7 openings

6 @ 9 3/4" clear

1 @ 11 1/4" clear

