



**System should be installed on solid concrete floor or VCT covered concrete floor.**  
**Any existing carpet must be removed prior to installation at the rail locations.**

**Floor levelness should meet standard General Contractor code of 1/8" over 10'.**

**Elevation**  
**77 3/4" uprights**  
**7 openings**  
**6 @ 9 3/4" clear**  
**1 @ 11 1/4" clear**

